

(These items were developed by teachers for the Technical Skills Assessment. Below is a sample item for each program standard.)

### Question 1 of 12

Which procedure is NOT important during a crane lift?

- A) Restrict worker activity in the lift zone.
- B) Notify the entire site that a lift is occurring.
- C) Clear the site.
- D) Review hand signals with the crane operator.

### Question 2 of 12

What action SHOULD be taken if a worker is plugging in an extension cord and notices the grounding plug is missing?

- A) Put the cord back in the trailer and get another one.
- B) Notify supervisor and dispose of the cord.
- C) Use a battery-operated tool.
- D) Connect that cord to another one with a grounding plug.

### Question 3 of 12

In what view is a floor plan drawn?

- A) Street
- B) Facing north
- C) Elevated
- D) Top

#### Question 4 of 12

Which area describes the space between the property line and where construction may take place?

- A) No-build zone
- B) Gray area
- C) Proximity
- D) Setback

#### Question 5 of 12

Which type of nail is BEST for attaching subfloor to flooring joists?

- A) Box
- B) Common
- C) Underlayment
- D) Sinkers

#### Question 6 of 12

How many inches on center (o.c.) is typical stud spacing in a wood framed wall?

- A) 16"
- B) 19"
- C) 15"
- D) 13"

#### Question 7 of 12

What other rafter is much the same in laying out the bird's mouth for a hip rafter?

- A) Hip
- B) Common
- C) Plumb
- D) Seat

### Question 8 of 12

What type of PPE is NOT required to be worn when installing insulation?

---

- A) Gloves
- B) Safety glasses/goggles
- C) Earplugs
- D) Mask

### Question 9 of 12

Which term refers to the area under the roof overhang?

---

- A) Frieze
- B) Facia
- C) Gable
- D) Soffit

### Question 10 of 12

What MUST be checked before installing door handles?

---

- A) Door swing
- B) Door size
- C) Door style
- D) Door weight

### Question 11 of 12

Normally, how thick is regular core drywall used for residential construction?

---

- A) 3/8"
- B) 1/4"
- C) 1/2"
- D) 1/8"

## Question 12 of 12

Which trim pieces should be installed first?

---

- A) Baseboards
- B) Door casings
- C) Chair rails
- D) Moldings

Carpentry Sample Test Answer Key

<b>Question</b>	<b>Answer</b>
1.	A
2.	B
3.	D
4.	D
5.	C
6.	A
7.	B
8.	C
9.	D
10.	A
11.	C
12.	B